



भारत संचार निगम लिमिटेड
(भारत सरकार का उपक्रम)
BHARAT SANCHAR NIGAM LIMITED
(A Govt. of India Enterprise)

**O/o The Executive Engineer, BSNL Civil Division, Quarter No: 3 & 4, II Floor, D-Tax Building,
VELAMPETA, VISAKHAPTAM, A.P.(Ph. No. 0891-257090/2787711),
Email: cecivilapeevm@gmail.com**

Lr. No. 5(4)/NIQ/BSNL CD/VM/2020-121/172

Dated 26.06.2020.

NOTICE INVITING QUOTATION
NIQ No: 01/2020-21

The Executive Engineer ©, BSNL Civil Division, Quarter No : 3 & 4, 2nd Floor, D-Tax Building, VELAMPETA, VISAKHAPATNAM invites Wax Sealed Quotations for the following work on behalf of BHARAT SANCHAR NIGAM LIMITED (A Government of India Enterprise) from all eligible BSNL registered contractors & non-BNSL registered contractors of Public works Organizations like CPWD / A.P. State PWD (R&B) / DOP / MES / Railways only up to 15.00 Hrs on or before **04.07.2020** and will be opened a 15:30 Hrs on the same day.

Name of the work: Dismantling of 2 nos 15M MARR MAST Towers (including foundation and BTS bed) at VIMAN NAGAR, Visakhapatnam including transportation of MARR mast material from Viman Nagar site to Telephone Exchange, CRR Nagar Compound, Visakhapatnam.


Estimated cost : Rs. 42, 627/-

As per schedule Enclosed.

Conditions:


1. Intending tenderers shall submit Self Attested copies of (i) Registration (ii) Form "A" and Partnership deed in case of partnership firms and Memorandum of Articles of Association and Power of Attorney to sign the tender documents in case of Private Limited companies (iii) PAN CARD issued by the Income Tax Department iv) Certificate of Registration for GST
2. Work is of urgent nature and to be executed on top priority.
3. The work shall be completed as per CPWD Specifications 2009 and as per directions of the Engineer-in-charge.
4. The contractor shall remove all scaffoldings, materials, rubbish and malba on completion of the work.
5. The rate quoted shall include all operations such as material, labour, transportation and incidentals etc., and nothing extra will be paid.
6. Any damage to BSNL property shall be made good at his own cost.
7. Time allowed for completion of the work is **15 (Fifteen) Days**.
8. BSNL reserves the right to accept or reject whole or part of the work without assigning any reasons.
9. Bill will be paid on completion of the work only.
10. Payment will be made by NEFT thorough ERP.
11. The rates quoted shall be inclusive of GST and all other applicable Taxes.

CONTRACTOR


Executive Engineer©
BSNL Civil Division, Visakhapatnam

Copy to

1. The General Manager, BSNL Telecom District, Visakhapatnam
2. The Superintending Engineer (Civil), BSNL Civil Circle, Visakhapatnam
3. The Sub Divisional Engineer (Civil), BSNL CSD I & II VM/VZM/SKLM
4. The A.O. / Auditor of BSNL CD, VM


Executive Engineer

SCHEDULE OF QUANTITIES

Name of the work: Dismantling of 2 nos 15M MARR MAST Towers (including foundation and BTS bed) at VIMAN NAGAR, Visakhapatnam including transportation of MARR mast material from Viman Nagar site to Telephone Exchange, CRR Nagar Compound, Visakhapatnam.						
I.No.	Description of Item	Quantity		Rate (Rs)	Unit	Amount (Rs)
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.					
	A) Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.50	Cum		One Cubic Metre	
	Rate in Words					
2	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.					
		1.50	Cum		One Cubic Metre	
	Rate in Words					
3	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.					
	A) In cement mortar	2.50	Cum		One Cubic Metre	
	Rate in Words					
4	Extra for providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer's specification.					
		3.00	units		per 50 kg cement	
	Rate in Words					
5	Cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement.					
	A) 12 mm cement plaster	15.00	Sqm		One Square Metre	
	Rate in Words					
6	White washing with lime to give an even shade:					
	A) New work (three or more coats)	15.00	Sqm		One Square Metre	
	Rate in Words					

7	Dismantling and de-hoisting of MARR MAST Tower comprises angles, pipes, plates bolts and nuts and antenna mounts etc., including cutting anchor fasteners, dismembering horizontal bracing supports at four levels and Horizontal/ Vertical Gantry with the help of pulleys and ropes and stacked the material on the terrace, lowering the Tower & Gantry material from the terrace to the ground level with the help of ropes and pulleys including watch and ward till completion of transportation / handing over the material complete as directed by the Engineer-in-Charge.						
	(A) 15M height MARR MAST	2.00	Nos.		Each		
	Rate in Words						
8	Transportation and stacking of dismantled MARR MAST Tower Material comprises, angles, pipes, plates, bolts, nuts, stays, antenna mounts etc., including horizontal gantry material from the Viman Nagar site to Telephone Exchange, CRR Nagar Compound, Visakhapatnam (Up to 15 KM) by mechanical transport including lowering the material from the terrace to the ground level with the help of ropes and pulleys, loading and unloading etc., complete as directed by the Engineer-in-Charge.	1.00	job		One Job		
	Rate in Words						
9	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including bringing the dismantled from floor IV level to the ground level, loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge,15Km lead, for all leads including all lifts involved.	4.50	Cum		One Cubic Metre		
	Rate in Words						
10	Credit for taking away the old and rusted reinforcement bars obtained from the demolishing of RCC Columns and Beams of 40M GBT etc., complete as directed by the Engineer - in - charge.	55.00	Kg		One Kilogram		
	Rate in Words						
					Total :		
	Total in Words						

(CONTRACTOR)

Executive Engineer ©
BSNL Civil Division
Visakhapatnam