

BHARAT SANCHAR NIGAM LIMITED

(A Govt. of India Enterprise)

Office of the Sub Division Engineer (E), Electrical Sub Division-Tirupati

2nd floor, New Admin Building, Tirupati

No:- 9(21)/BSNL/EDT/2023-24/229

Dated: 29.02.2024

NOTICE INVITING QUOTATION(SPOT QUOTATION)

NIQ No: 10/BSNL/EDT/23-24 Dated : 29.02.2024

The Executive Engineer (Electrical), BSNL, Electrical Division - Tirupati invites on behalf of the Bharat Sanchar Nigam Limited sealed item rate spot quotation from BSNL enlisted Contractors/Agency having valid Electrical License up to 15.00 Hrs. on. **01.03.2024** for following works :

S.No	Name of work:-	Estimated Amount
1	Name of Work: Restoration of Earthing at different RAN sites under Phase IX.2 4G project under Tirupati Business Area of BSNL (Phase II) (Lightning arrestor for for March 24 sites)	Rs 109740/- (ic GST)

schedule of above work ::

Sr. No.	Description of items	Qty.	Rate Rs.	Unit	Amount Rs.
As per sheet attached --					
Total Rs.					

The quotation will be opened on the same day as given above at 15.30 Hrs.

Condition :-

- 1 The work shall be carried out as per the CPWD specification.
- 2 The materials shall be got approved by the Engineer-in Charge.
- 3 **The work shall be carried out within One Month**
- 4 The agency should have valid Electrical License.
- 5 The firm should attach self attested documents pertaining to the eligibility criteria to the quotations.

Contractor

Executive Engineer(E)
BSNL Electrical Division
Tirupati

TO
Executive Engineer(E)
BSNL Electrical Division
Tirupati

NOTICE INVITING QUOTATION(SPOT QUOTATIONS)					
NIQ No: 10/BSNL/EDT/23-24 Dated : 29.02.2024					

Name of Work: Restoration of Earthing at different RAN sites under Phase IX.2 4G project under Tirupati Business Area of BSNL (Phase II) (Ligtning arrestor for for March 24 sites)						
S.No	Description of Item	Qty		Rate	Unit	Amount in Rs
1	Providing and fixing of lightning conductor finial made of 25mm dia 1000 mm long GI pipe (B-class) having single prong at top of the tower with suitable size GI base plate including holes etc.complete as required.	13	Jobs		Job	
2	Providing and fixing 50mm X 3mm G.I. strip along the tower/Wall with suitable insulators fixed at required interval etc.,as required.(For Vertical Run)	100	Mtr		Mtr	
3	Providing and fixing 25mm X 3mm G.I. strip along the tower/Wall with suitable insulators fixed at required interval etc.,as required.(For Vertical Run)	100	Mtr		Mtr	
4	Providing and fixing of the 300mm x 50mm x 10 mm thick GI bus bar on surface of wall on suitable insulators as main earth bus bar having required no of holes for connections complete as reqd	5	Jobs		Job	
	ADD CGST @9%					
	ADD SGST@9%					
	Total value of work (INcluding GST)					

Contractor

Executive Engineer (E)
BSNL Electrical Division
Tirupathi

Site Names for LA

Trp Sp Office
Trptuda2Ndbts
Trp Spmcollege
Trp Khadicolony
Trp Bazarstreet
Trp Jeevakona
Keshavayanagunta
Rangampet Ptc
Kvbpuram
Vrkuppam
Kosuvapalli Uso
Vijayapuram
Avanthi