

BHARAT SANCHAR NIGAM LIMITED

(A Govt. of India Enterprise)

Office of the Sub Division Engineer (E), Electrical Sub Division-Tirupati

2nd floor, New Admin Building, Tirupati

No:- 9(21)/BSNL/EDT/2023-24/228

Dated: 29.02.2024

NOTICE INVITING QUOTATION(SPOT QUOTATION)

NIQ No: 09/BSNL/EDT/23-24 Dated : 29.02.2024

The Executive Engineer (Electrical), BSNL, Electrical Division - Tirupati invites on behalf of the Bharat Sanchar Nigam Limited sealed item rate spot quotation from BSNL enlisted Contractors/Agency having valid Electrical License up to 15.00 Hrs. on. **01.03.2024** for following works :

S.No	Name of work:-	Estimated Amount
1	Name of Work: Restoration of Earthing at different RAN sites under Phase IX.2 4G project under Tirupati Business Area of BSNL (Phase II) (Earthing for March 24 sites)	Rs 147925/- (ic GST)

schedule of above work ::

Sr. No.	Description of items	Qty.	Rate Rs.	Unit	Amount Rs.
As per sheet attached --					
Total Rs.					

The quotation will be opened on the same day as given above at 15.30 Hrs.

Condition :-

- 1 The work shall be carried out as per the CPWD specification.
- 2 The materials shall be got approved by the Engineer-in Charge.
- 3 **The work shall be carried out within One Month**
- 4 The agency should have valid Electrical License.
- 5 The firm should attach self attested documents pertaining to the eligibility criteria to the quotations.

Contractor

**Executive Engineer(E)
BSNL Electrical Division
Tirupati**

TO
Executive Engineer(E)
BSNL Electrical Division
Tirupati

NOTICE INVITING QUOTATION (SPOT QUOTATIONS)

NIQ No: 09/BSNL/EDT/23-24 Dated : 29.02.2024

Name of Work: Restoration of Earthing at different RAN sites under Phase IX.2 4G project under Tirupati Business Area of BSNL (Phase II) (Earthing for March 24 sites)

S.No	Description of Item	Qty	Rate	Unit	Amount in Rs
1	Earthing with 4 Nos plates by observing the following procedure.				
	a) Digging of earthing pit of suitable size and up to 5' deep and refilling the same after installing the earth plate.				
	b) Supplying and installing 4nos GI earth plates of size 600 X 600 X 6mm thick.				
	c) Drilling holes to the sheets making connections to all the four sheets for extending earthings using GI bolts and nuts, washers, spring washers etc.,				
	d) Providing 2" dia GI Pipe (B class) of approx length 3 feet with suitable GI sheet funnel.				
	e) Providing necessary enclosure/earth pit with pre-caset RCC chamber, with at least 50 mm thick RCC top cover plate, white washing of the masonry enclosure and sign writing etc., as required. (Size of masonry enclosure 450 mm x 450 mm).				
	f). Charcoal - 100 kgs salt-- 25 kgs				
	g). S/F of 4Nos 25x5 mm size GI strips from base of GI plates to upto a height of 5 feet i/c loop earthing of 4 plates in the pit				
	h) initial watering of the earth pit arrangement and arranging manpower for testing the earth resistance and furnishing the test results.	4	Job	Job	
2	Digging of addl. depth for above earth pit and S/F of 4Nos 25x5 mm GI strips as reqd.	20	Feet	Foot	
3	Providing and fixing following size G.I. strip on surface or in recess for connections etc. as required.				
a	25 mm dia PVC pipe	20	Mtrs	Mtr	
b	25 sqmm Copper cable lugs	8	nos	each	
c	25 sqmm PVC insulated copper conductor cable	24	Mtrs	Mtr	
	ADD CGST @9%				
	ADD SGST@9%				
	Total value of work (Including GST)				

Contractor

Executive Engineer (E)
BSNL Electrical Division
Tirupathi

Site Names
Devalampeta
Maddinayanipalli_Usa
Kona
C. Kalepalli_Usa