



**O/o The Executive Engineer, BSNL Civil Division, Second Floor, New Admn. Building,  
HPO Compound, TIRUPATI, A.P. - 517501, (Ph. No. 0877-2241900/2221880),  
Email: cecivilapeetpt@gmail.com**

**Lr. No.NIQ(21)Vol-III/CDT/2020-21/90**

**Dated: 31.08.2020.**

**NOTICE INVITING QUOTATION**  
**NIQ No: 02/2020-21**

The Executive Engineer (C), BSNL Civil Division, Second Floor, New Admn. Building, HPO Compound, TIRUPATI, A.P. -517501 invites Wax Sealed Quotations for the following work on behalf of BHARAT SANCHAR NIGAM LIMITED (A Government of India Enterprise) from all eligible BSNL registered contractors & non-BSNL registered contractors of Public works Organizations like CPWD / A.P. State PWD (R&B) / DOP / MES / Railways only up to 15.00 Hrs on or before **08.09.2020** and will be opened a 15:30 Hrs on the same day.

**Name of the work: Annual Maintenance of 40 M GB tower at R.S.Pendekallu in Kurnool District.**

**Estimated cost : Rs. 47, 349/-**

---

As per schedule enclosed.

---

**Conditions:**

1. Intending tenderers shall submit Self Attested copies of (i) Registration (ii) Form "A" and Partnership deed in case of partnership firms and Memorandum of Articles of Association and Power of Attorney to sign the tender documents in case of Private Limited companies (iii) PAN CARD issued by the Income Tax Department (iv) Certificate of Registration for **GST**.
2. Work is of urgent nature and to be executed on top priority.
3. The work shall be completed as per CPWD Specifications 2009 and as per directions of the Engineer-in-charge.
4. The contractor shall remove all scaffoldings, materials, rubbish and malba on completion of the work.
5. The rate quoted shall include all operations such as material, labour, transportation and incidentals etc., and nothing extra will be paid.
6. Any damage to BSNL property shall be made good at his own cost.
7. Time allowed for completion of the work is **15 (Fifteen) Days**.
8. BSNL reserves the right to accept or reject whole or part of the work without assigning any reasons.
9. Bill will be paid on completion of the work only.
10. Payment will be made by NEFT thorough ERP.
11. The rates quoted shall be inclusive of GST and all other applicable Taxes.

**CONTRACTOR**

**Executive Engineer (C),  
BSNL Civil Division, Tirupati.**

**Copy to**

1. The Pr. General Manager, Telecom District, BSNL, Kurnool.
2. The Superintending Engineer (Civil), BSNL Civil Circle, Vijayawada.
3. The Sub Divisional Engineer (Civil), BSNL Civil Sub Division, Kurnool, Anantapur, Tirupati - I & II/ Nellore/ Kadapa.
4. The A.O. / Auditor of BSNL Civil Division, Tirupati.

**Executive Engineer (C),  
BSNL Civil Division, Tirupati.**

## SCHEDULE OF QUANTITIES

**Name of work :- Annual Maintenance of 40 M GB tower at R.S,Pendekallu in Kurnool District.**

I.No.	Description of Item	Quantity		Rate (Rs)	Unit	Amount (Rs)
1	Labour charges for marking the centre points at different levels on the tower and assistance for checking the verticality of tower and labour charges for tightening of nuts and bolts of all tower components like angles, flats, pipes and all dia tower bolts including cable ladder and climbing ladder etc., including arranging ropes, pulleys, glouses, helmets for the labour engaged for the tower tightening work. The department at no cost responsible for the accidents, damages etc., if any occurred during the execution of work. The work should be carried out as per the direction of the Engineer-in-charge. The agency shall take necessary insurance for workmen compensation and all risks coverage.					
	a) 40 M GBT (Weight about 9.50 MT)	1.00	Job		One Job	
	<b>Rate in Words .....</b>					
2	Labour charges for making tower members (Vertical ladder components such as safety rings, vertical flats and plat form railings etc.,) in good condition including cost of dismembering and making good at any height of Ground Based Tower and necessary alterations using welding machine / drilling machine etc., complete and fixing in same position with bolt & nuts as per the directions of the Engineer-in-charge. (Rate includes transportation of welding machine / drilling machine to site).	1.00	Job		One Job	
	<b>Rate in Words .....</b>					
3	Structural steel work riveted, bolted or welded in build up sections, trusses and framed work, including cutting, hoisting, fixing in position with galvanized steel sections consisting of angles, flats, plates fabricated as per approved drawings in gratings, frames, railings, cable trays, ladders, space frames and similar locations. The galvanizing shall be as per IS 4759 with average mass of zinc coating of 610 gm/Sqm (approximately 85 micron). The steel sections shall be of M.S grade 'A' as per IS 2062. Cost of galvanization is inclusive. The payment shall be made as per the standard structural steel tables for the bare steel sectional weights. All compete as directed by the Engineer -in-charge.	50.00	Kgs		One Kilogram	
	<b>Rate in Words .....</b>					

4	Supplying and fixing of galvanised high tension grip bolts and nuts of grade 5.6 and of required size minimum mass of galvanised coating not less than 610 gms per sqm on bolts and nuts and other fasteners etc., (Galvanisation shall be hot dipped as per IS : 1759 standard / Zinc galvanising should be conform to IS :13229-1991 or IS 209-1992.)	40.00	Kgs		One Kilogram	
<b>Rate in Words .....</b>						
					<b>Total :</b>	
<b>Total in Words .....</b>						

(CONTRACTOR)

**Executive Engineer (C),  
BSNL Civil Division  
Tirupati.**