



**O/o The Executive Engineer, BSNL Civil Division, Second Floor, New Admn. Building,
HPO Compound, TIRUPATI, A.P. – 517501, (Ph. No. 0877-2241900/2221880),
Email: cecivilapeetpt@gmail.com**

Lr. No.NIQ(21)Vol-III/CDT/2020-21/92

Dated:31.08.2020.

NOTICE INVITING QUOTATION
NIQ No: 04/2020-21

The Executive Engineer (C), BSNL Civil Division, Second Floor, New Admn. Building, HPO Compound, TIRUPATI, A.P. -517501 invites Wax Sealed Quotations for the following work on behalf of BHARAT SANCHAR NIGAM LIMITED (A Government of India Enterprise) from all eligible BSNL registered contractors & non-BSNL registered contractors of Public works Organizations like CPWD / A.P. State PWD (R&B) / DOP / MES / Railways only up to 15.00 Hrs on or before **08.09.2020** and will be opened a **15:30 Hrs** on the same day.

Name of the work: Providing ladder& Annual Maintenance to 40M GB Tower at Veldurthy in Kurnool District.

Estimated cost : ₹72,165/-

As per schedule enclosed.

Conditions:

1. Intending tenderers shall submit Self Attested copies of (i) Registration (ii) Form “A” and Partnership deed in case of partnership firms and Memorandum of Articles of Association and Power of Attorney to sign the tender documents in case of Private Limited companies (iii) PAN CARD issued by the Income Tax Department (iv) Certificate of Registration for **GST**.
2. Work is of urgent nature and to be executed on top priority.
3. The work shall be completed as per CPWD Specifications 2009 and as per directions of the Engineer-in-charge.
4. The contractor shall remove all scaffoldings, materials, rubbish and malba on completion of the work.
5. The rate quoted shall include all operations such as material, labour, transportation and incidentals etc., and nothing extra will be paid.
6. Any damage to BSNL property shall be made good at his own cost.
7. Time allowed for completion of the work is **15 (Fifteen) Days**.
8. BSNL reserves the right to accept or reject whole or part of the work without assigning any reasons.
9. Bill will be paid on completion of the work only.
10. Payment will be made by NEFT thorough ERP.
11. The rates quoted shall be inclusive of GST and all other applicable Taxes.

CONTRACTOR

Executive Engineer (Civil),
BSNL Civil Division,
TIRUPATI.

Copy to

1. The Pr. General Manager, Telecom District, BSNL, Kurnool.
2. The Superintending Engineer (Civil), BSNL Civil Circle, Vijayawada.
3. The Sub Divisional Engineer (Civil), BSNL Civil Sub Division, Kurnool, Anantapur, Tirupati - I & II/
Nellore/ Kadapa.
4. The A.O. / Auditor of BSNL Civil Division, Tirupati.

Executive Engineer (Civil),
BSNL Civil Division,
TIRUPATI.

SCHEDULE OF QUANTITIES

Name of work :- Providing ladder& Annual Maintenance to 40M GB Tower at Veldurthy in Kurnool District.

Item No.	DESCRIPTION OF ITEM	Quantity	Rate	UNIT	AMOUNT
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m aboveground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	230.00	Sqm	One Sqm	
<p>Rate in words</p>					
2	Finishing walls with Acrylic Smooth exterior paint of required shade :				
	a) Old work (Two or more coat applied @ 1.67 ltr / 10 sqm) on existing cement paint surface.	20.00	Sqm	One Sqm	
<p>Rate in Words</p>					
3	Labour charges for marking the centre points at different levels on the tower and assistance for checking the verticality of tower and labour charges for tightening of nuts and bolts of all tower components like angles, flats, pipes and all dia tower bolts including cable ladder and climbing ladder etc., including arranging ropes, pullies, glouses, helmets for the labour engaged for the tower tightening work.The department at no cost responsible for the accidents, damages etc., if any occurred during the execution of work. The work should be carried out as per the direction of the Engineer -in- charge. The agency shall take necessary insurance for workmen compensation and all risks coverage.				
	a) 40 M GBT (Weight about 9.50 MT)	1.00	Job	One Job	
<p>Rate in Words</p>					
4	Painting one or more coat with high glass synthetic enamel paint of approved brand and manufacture of required colour to give an even shade for specified masts / towers complete as per the directions of the Engineer in charge.				
	a) 40 M GBT	1.00	Job	Each	
<p>Rate in Words</p>					

5	Labour charges for fixing of ladder and its components to 40 M GB Tower with supplied materials such as ladders, safety rings, vertical flats, connecting components to towers, clamps, bolts and nuts, etc., in good condition including necessary alterations for fixing of ladder to tower, necessary alterations such as welding using welding machine, making holes using drilling machine etc., all complete as per the directions of the Engineer-in-charge. (Rate includes transportation of welding machine / drilling machine to site and back).	1.00	Job			One job
Rate in Words						
6	Structural steel work riveted, bolted or welded in build up sections, trusses and framed work, including cutting, hoisting, fixing in position with galvanized steel sections consisting of angles, flats, plates fabricated as per approved drawings in gratings, frames, railings, cable trays, ladders, space frames and similar locations. The galvanizing shall be as per IS 4759 with average mass of zinc coating of 610 gm/Sqm (approximately 85 micron). The steel sections shall be of M.S grade 'A' as per IS 2062. Cost of galvanization is inclusive. The payment shall be made as per the standard structural steel tables for the bare steel sectional weights. All complete as directed by the Engineer -in-charge.	30.00	Kgs			One Kilogram
Rate in Words						
7	Supplying and fixing of galvanised high tension grip bolts and nuts of grade 5.6 and of required size minimum mass of galvanised coating not less than 610 gms per sqm on bolts and nuts and other fasteners etc., (Galvanisation shall be hot dipped as per IS : 1759 standard / Zinc galvanising should be conform to IS :13229-1991 or IS 209-1992.)	50.00	Kgs			One Kilogram
Rate in Words						

8	Mechanical transportation of ladder and its components of tower members comprising MS angles, flats, plates, pipes, bolts and nuts, etc., of varying sizes and lengths from specified place to work site. The entire lot of tower members shall be transported in a single lot. The Job includes cost of collection of all tower members from Telecom store yard at Nandyal check post, Kurnool, loading and unloading and depositing the tower members near tower in TE compound at Veldurthy complete as per directions of Engineer -in-charge. (Nothing extra shall be paid over and above the rate on any account).					
	a) Within the lead of 20.00 KM.	1.00	Job		One Job	
	Rate in Words					
	b) Extra over above item for transportation beyond the lead of 20.00 KM.	20.00	KMs		One KM	
	Rate in Words					
					Total :	
	Total in Words					

(CONTRACTOR)

Executive Engineer (Civil),

BSNL Civil Division,

Tirupati