

**Office of the Executive Engineer (Civil), BSNL Civil Division,
First Floor, Sanchar Bhvan, Near Gokavaram Bus stand, Rajamahendravaram-533104**

Lr. No. 63(5)/EE/BSNL/CD/RMVM/2023-24/114

dated: 15.09.2023

NOTICE INVITING QUOTATION
NIQ No.12/BSNL/CD/RMVM/2023-24

The Executive Engineer (Civil), BSNL Civil Division, First Floor, Sanchar Bhvan, Near Gokavaram Bus stand, Rajamahendravaram-533104 invites Wax sealed quotations for the following work on behalf of BSNL from the eligible BSNL registered contractors & Non BSNL registered Contractors of Public Works organizations like CPWD/A.P State PWD(R&B)/DOP/MES/Railways only upto 1500 hrs on or before 25.09.2023 and the same will be opened on the same day at 1530 hrs .

Name of Work: Providing Aluminium partition and miscellaneous items in TRA section(Ground floor) at Sanchar Bhavan, Rajamahendravaram

Estimated cost: Rs.80,562/-

S.No.	Description of Item	Quantity	Rate	Unit	Amount
As per sheet Enclosed					

CONDITIONS:

1. Intending tenderers shall submit Self Attested copies of (i) Registration (ii) Form “A” and Partnership deed in case of partnership firms and Memorandum of Articles of Association and Power of Attorney to sign the tender documents in case of Private Limited companies (iii) PAN CARD issued by the Income Tax Department (iv) Certificate of Registration for **GST**.
2. Work is of urgent nature and to be executed on top priority.
3. The work shall be completed as per CPWD Specifications 2009 and as per directions of the Engineer-in-charge.
4. The contractor shall remove all scaffoldings, materials, rubbish and malba on completion of the work.
5. The rate quoted shall include all operations such as material, labour, transportation and incidentals etc., and nothing extra will be paid.
6. Any damage to BSNL property shall be made good at his own cost.
7. Time allowed for completion of the work is **15 (fifteen) days**.
8. BSNL reserves the right to accept or reject whole or part of the work without assigning any reasons.
9. Bill will be paid on completion of the work only.
10. Payment will be made by NEFT thorough ERP.
11. The rates quoted shall be inclusive of GST and all other applicable Taxes.

Signature of the Contractor

**Executive Engineer(Civil),
BSNL Civil Division,
Rajamahendravaram**

Copy to

1. The Pr. General Manager, Telecom District, BSNL, Rajamahendravaram
2. The Superintending Engineer (Civil), BSNL Civil Circle, Vijayawada.
- 3 & 4 . The Sub Divisional Engineer (Civil), BSNL Civil Sub Division, Rajamahendravaram/Eluru.
- 10 & 11. The A.O. / Auditor of BSNL Civil Division, Rajamahendravaram.

**Executive Engineer (C),
BSNL Civil Division,
Rajamahendravaram**

SCHEDULE OF QUANTITIES

Name of work: Providing Aluminium partition and miscellaneous items in TRA section (Ground floor) at Sanchar Bhavan, Rajamahendravaram.

I.No.	Description of Item	Quantity	Rate (Rs)	Unit	Amount (Rs)
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.				
a)	In cement mortar	1.00 Cum		One Cubic Metre	
	Rate in words:(Rupees)				
2	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	1.00 Cum		One Cubic Metre	
	Rate in words:(Rupees)				
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	100.00 Kg		One Kilogram	
	Rate in words:(Rupees)				
4	12 mm cement plaster of mix :				
a)	1:6 (1 cement: 6 fine sand)	5.00 Sqm		One Square Metre	
	Rate in words:(Rupees)				
5	Finishing walls with Acrylic Smooth exterior paint of required shade :				
a)	New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm).	50.00 Sqm		One Square Metre	
	Rate in words:(Rupees)				

- 6 Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per directions of Engineer-In-Charge.
- a) With cement mortar 1:4 (1 cement : 4 fine sand). 5.00 Sqm One Square Metre

Rate in words:(Rupees)

- 7 Fixing existing aluminium partitions/door /windows at Sanchar bhavan building(G+4) Rajahmundry in different floors including cutting the existing glass panes, Nova pan boards, Aluminium sections, Snap beadings, Rubber, drilling the floor, nails, Aluminum L sections,carriage of required material from one floor to another floor etc complete all as per the directions of Engineer in charge. 55.00 Sqm One Square Metre

Rate in words:(Rupees)

Contractor

Executive Engineer(civil)