



O/o the Executive Engineer(E)
BSNL Electrical Division,6th floor, BSNL staff quarters,
D-TAX building Velampeta,Visakhapatnam-530001,
Ph:0891 2544604.
Email: eeevizagbsnl@gmail.com

Lr.No:NIQ / BSNL / EDVM / 2020-2021/ 290

Dt: 11.11.2020

NOTICE INVITING QUOTATION No: 01/ BSNL / EDVM/ 2020-2021

The Sealed Item rate quotations are hereby invited by the Executive Engineer(E), BSNL Electrical Division,6th floor, BSNL staff quarters,D-TAX building Velampeta, Visakhapatnam-530001 on behalf of the Chairman, BSNL from the BSNL Enlisted contractors /agency who has carried out atleast one electrical work in BSNL/any other PSU/ Central/State Government having valid Electrical license.The sealed quotations should always be placed in a sealed cover with the name of work written on the envelope will be received by the EE(E) BSNL ED,VISAKHAPATNAM upto 15-00 hrs on **16.11.2020** and will be opened by him on the same day at 15-30 hours.

Name of work:-SITC of Turbo Air Ventilator Systems for various BTS Stations under East Godavari SSA SH: SITC of Free cooling arrangement with Exhaust fans.(3 sites)

Sr.No	Description of item	Qty	Rate	Unit	Amount
1	Supplying and fixing of 12" Heavy duty exhaust fan with nominal speed of 1400 RPM suitable for operation on 230V, 50HZ AC Supply i/c drilling holes, providing fixing bolts and nuts etc., as required. (M/s. Almonard /Havells/ Crompton /Orient/Usha Smlr supr Make)	1 No		Each	
2	Supplying & fixing 2 Nos. 25 x 5 mm MS/GI Flats of 35 cms each on surface of wall / PVC wall panel (for fixing of the exhaust fan) including drilling holes etc., as required.	1 job		job	
3	Providing opening of suitable size to the brick wall or PVC wall panel for fixing of the above 12" exhaust fan by cutting & making good the same etc., as required	1 job		Job	
4	Supplying and laying of 3 core 1.5 sq. mm PVC insulated copper conductor cable as required.	5 Mtrs		Mtr	
5	Supplying and fixing of the analog time switch suitable for operation on 230V, 50HZ AC Supply etc., on surface of wall/ shelter wall panel as required. (M/s. L&T model FM-1 Quartz / Smlr supr model and make)	1 No		Each	

- | | | | |
|---|---|------|------|
| 6 | Supplying and fixing of exhaust fan shutter suitable for 12" exhaust fan made with suitable 22 guage GI sheet i/c cutting, bending, welding, painting etc as required. (Will be provided wherever required) | 1 No | Each |
| 7 | Supplying and fixing of prefabricated Louvers frame of size 600 mm X 300 mm , made out of MS sheet and welded with GI wire mesh (1inch x 1Inch) in the back side on surface of wall/ PVC wall panel of shelter i/c making opening by cutting , finishing with suitable sealant complete as reqd. (for fresh air arrangement) | 1 No | Each |

Total for 1 site
Total for 03 sites

Total Rs.
Add GST 18% of Total _____
Grand Total Rs.

Note:

- 1 The work shall be carried out as per the CPWD specification.
- 2 The materials shall be got approved by the Engineer-in Charge.
- 3 The work shall be carried out within 15 days.
- 4 The agency should have valid Electrical license.
- 5 The firm should attach self attested documents pertaining to the eligibility criteria to the quotations.

CONTRACTOR

EXECUTIVE ENGINEER(E)
BSNL ELECTRICAL DIVISION
VISA KHAPATNAM