



BHARAT SANCHAR NIGAM LIMITED
(A Government of India Enterprises)
Office of the Executive Engineer, BSNL Civil Division,
2nd Floor New Administrative Building, Beside HPO Compound, Tirupati-517201

Lr. No. NIQ(21)/2024-25/CDT/191

Dated: 10.06.2024.

NOTICE INVITING QUOTATION
NIQ No.02/CDT/2024-25

The Executive Engineer (Civil), BSNL Civil Division, Second Floor, New Administrative Building, HPO Compound, Tirupati-AP-517501 invites Wax sealed quotations for the following work on behalf of BSNL from the eligible BSNL registered Contractors & Non BSNL registered Contractors of Public Works organizations like CPWD/A.P State PWD(R&B)/DOP/MES/Railways only upto 15:00 hrs on or before 20.06.2024 and the same will be opened on the same day at 15:30 hrs.

Name of Work: "Maintenance of 40M GB Tower at Vikruthamala and 9M Pole at Satrawada in Chittoor BA"

Estimated cost: Rs.63,108/-


S.No.	Description of Item	Quantity	Rate	Unit	Amount
As per sheet Enclosed					

Conditions:

1. Intending tenderers shall submit Self Attested copies of (i) Registration (ii) Form "A" and Partnership deed in case of partnership firms and Memorandum of Articles of Association and Power of Attorney to sign the tender documents in case of Private Limited companies (iii) PAN CARD issued by the Income Tax Department (iv) Certificate of Registration for GST.
2. Work is of urgent nature and to be executed on top priority.
3. The work shall be completed as per CPWD Specifications 2019 Vol.I&II and as per directions of the Engineer-in-charge.
4. The contractor shall remove all scaffolding, materials, rubbish and malba on completion of the work.
5. The rate quoted shall include all operations such as material, labour, transportation and incidentals etc., and nothing extra will be paid.
6. Any damage to BSNL property shall be made good at his own cost.
7. Time allowed for completion of the work is 15 Days.


8. BSNL reserves the right to accept or reject whole or part of the work without assigning any reasons.
9. Bill will be paid on completion of the work only.
10. Payment will be made by NEFT thorough ERP.
11. The rates quoted shall be inclusive of GST and all other applicable Taxes.

Signature of the Contractor


Executive Engineer(Civil),
BSNL Civil Division,
Tirupati.

Copy to :

- 1.The General Manager, Telecom District, BSNL, Tirupati, Chittoor BA.
- 2.The Superintending Engineer (Civil), BSNL Civil Circle, Vijayawada.
- 3 to 6 .The Sub Divisional Engineer (Civil), BSNL Civil Sub Division, Kurnool /Anantapur/ Tirupati /Nellore.
- 7 to 8. The A.O. / Auditor of BSNL Civil Division, Tirupati.


Executive Engineer (Civil),
BSNL Civil Division,
Tirupati.

SCHEDULE OF QUANTITIES

Name of work:- "Maintenance of 40M GB Tower at Vikruthamala and 9M Pole at Satrawada in Chittoor BA"

Item No.	DESCRIPTIONS	Quantity		Rate	UNIT	AMOUNT
1	Labour charges for marking the center points at different levels on the tower and assistance for checking the verticality of tower and labour charges for tightening of nuts and bolts of all tower components like angles, flats, pipes and all dia. tower bolts including cable ladder and climbing ladder etc., including arranging ropes, pullies, glouses, helmets for the labour engaged for the tower tightening work. The department at no cost responsible for the accidents, damages etc., if any occurred during the execution of work. The work should be carried out as per the direction of the Engineer -in- charge. The agency shall take necessary insurance for workmen compensation and all risks coverage.					
a)	40 M GBT (Weight up to 9.50 MT)	1.00	Job		Each	
	(Rupees					
2	Labour charges for making tower members (Vertical ladder components such as safety rings, vertical flats and plat form railings etc.,) in good condition including cost of dismembering and making good at any height of Ground Based Tower and necessary alterations using welding machine / drilling machine etc., complete and fixing in same position with bolt & nuts as per the directions of the Engineer-in-charge. (Rate includes transportation of welding machine / drilling machine to site).					
a)	For 40 M GBT	1.00	Job		Each	
	(Rupees					
3	Structural steel work riveted, bolted or welded in build up sections, trusses and framed work, including cutting, hoisting, fixing in position with galvanized steel sections consisting of angles, flats, plates fabricated as per approved drawings in gratings, frames,					

	railings, cable trays, ladders, space frames and similar locations. The galvanizing shall be as per IS 4759 with average mass of zinc coating of 610 gm/Sqm (approximately 85 micron). The steel sections shall be of M.S grade 'A' as per IS 2062. Cost of galvanization is inclusive. The payment shall be made as per the standard structural steel tables for the bare steel sectional weights. All compete as directed by the Engineer -in-charge.	40.00	Kgs		One Kg	
	(Rupees					
4	Supplying and fixing of galvanised high tension grip bolts and nuts of grade 5.6 and of required size minimum mass of galvanised coating not less than 610 gms per sqm on bolts and nuts and other fasteners etc., (Galvanisation shall be hot dipped as per IS : 1759 standard / Zinc galvanising should be conform to IS :13229-1991 or IS 209-1992.)	25.00	Kgs		One Kg	
	(Rupees					
5	Labour charges for tightening of nuts and bolts of all pole structure components like angles, flats, poles etc., including arranging ropes, pullies, glouses, helmets for the labour engaged for the pole tightening work. The department at no cost responsible for the accidents, damages etc., if any occurred during the execution of work. The work should be carried out as per the direction of the Engineer -in- charge. The agency shall take necessary insurance for workmen compensation and all risks coverage					
a)	For 9 M POLE	1.00	Job		Each	
	(Rupees					
					Total:	

Signature of the Contractor

Executive Engineer(Civil),
BSNL Civil Division,
Tirupati.