



BHARAT SANCHAR NIGAM LIMITED
(A Government of India Enterprises)
Office of the Executive Engineer, BSNL Civil Division,
2nd Floor New Administrative Building, Beside HPO Compound, Tirupati-517201

Lr. No. NIQ(21)/2024-25/CDT/92

Dated: 10.06.2024.

NOTICE INVITING QUOTATION
NIQ No.03/CDT/2024-25

The Executive Engineer (Civil), BSNL Civil Division, Second Floor, New Administrative Building, HPO Compound, Tirupati-AP-517501 invites Wax sealed quotations for the following work on behalf of BSNL from the eligible BSNL registered Contractors & Non BSNL registered Contractors of Public Works organizations like CPWD/A.P State PWD(R&B)/DOP/MES/Railways only upto 15:00 hrs on or before 20.06.2024 and the same will be opened on the same day at 15:30 hrs.

Name of Work: "Painting to GM Chamber and other miscellaneous works in GMTD Office, Tirupati."

Estimated cost: Rs.85,018/-

S.No.	Description of Item	Quantity	Rate	Unit	Amount
As per sheet Enclosed					

Conditions:

1. Intending tenderers shall submit Self Attested copies of (i) Registration (ii) Form "A" and Partnership deed in case of partnership firms and Memorandum of Articles of Association and Power of Attorney to sign the tender documents in case of Private Limited companies (iii) PAN CARD issued by the Income Tax Department (iv) Certificate of Registration for GST.
2. Work is of urgent nature and to be executed on top priority.
3. The work shall be completed as per CPWD Specifications 2019 Vol.I&II and as per directions of the Engineer-in-charge.
4. The contractor shall remove all scaffolding, materials, rubbish and malba on completion of the work.
5. The rate quoted shall include all operations such as material, labour, transportation and incidentals etc., and nothing extra will be paid.
6. Any damage to BSNL property shall be made good at his own cost.
7. Time allowed for completion of the work is 1(One) Month.

8. BSNL reserves the right to accept or reject whole or part of the work without assigning any reasons.
9. Bill will be paid on completion of the work only.
10. Payment will be made by NEFT thorough ERP.
11. The rates quoted shall be inclusive of GST and all other applicable Taxes.


Executive Engineer (Civil),
BSNL Civil Division,
Tirupati.

Signature of the Contractor

Copy to :

1. The General Manager, Telecom District, BSNL, Tirupati, Chittoor BA.
2. The Superintending Engineer (Civil), BSNL Civil Circle, Vijayawada.
- 3 to 6 .The Sub Divisional Engineer (Civil), BSNL Civil Sub Division, Kurnool /Anantapur/ Tirupati /Nellore.
- 7 to 8. The A.O. / Auditor of BSNL Civil Division, Tirupati.


Executive Engineer (Civil),
BSNL Civil Division,
Tirupati.

SCHEDULE OF QUANTITIES

Name of work:- " Painting to GM chamber and other miscellaneous works in GMTD Office, Tirupati."

Item No.	DESCRIPTIONS	Quantity		Rate	UNIT	AMOUNT
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :					
a)	1:2:4 (1 cement : 2 coarse sand(zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	0.60	Cum		One Cum	
(Rupees						
2	Providing and fixing aluminium tower bolts ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :					
a)	100x10 mm	4.00	Nos.		Each	
(Rupees						
3	Providing and fixing aluminium handles ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete :					
a)	100 mm	2.00	No.		Each	
(Rupees						
4	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	75.00	Sqm		One Sqm	
(Rupees						
5	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre. of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.					

a)	Two coats.	160.00	Sqm		One Sqm
	(Rupees				
6	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content.				
a)	With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre.	130.00	Sqm		One Sqm
	(Rupees				
7	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	21.00	Sqm		One Sqm
	(Rupees				
8	Dismantling wooden boardings in lining of walls and partitions, excluding supporting members but including stacking within 50metres lead :				
a)	Thickness above 10 mm up to 25 mm	7.00	Sqm		One Sqm
	(Rupees				
9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. : Internal work - Exposed on wall				
a)	20 mm nominal outer dia. Pipes.	10.00	mtr		One Metre
	(Rupees				
b)	32 mm nominal outer dia. Pipes.	2.00	mtr		One Metre
	(Rupees				
10	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :				
a)	40 mm nominal bore	1.00	No.		Each
	(Rupees				
11	Providing and fixing PTMT bib cock of approved quality and colour.				

a)	15mm nominal bore, 86 mm long. Weighing not less than 88 gms.	2.00	Nos.		Each	
(Rupees						
12	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :					
For fixed portion						
a)	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	11.00	Kg		One Kg.	
(Rupees						
13	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately).					
a)	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	10.00	Kg		One Kg.	
(Rupees						
14	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):					
a)	With float glass panes of 4.0 mm	1.00	Sqm		One Sqm	

	thickness (weight not less than 10 kg/sqm)					
	(Rupees					
15	Providing and fixing CPVC female threaded adapter (FTA) for water supply line ,fittings of approved quality and colour.	2.00	Nos.		Each	
	(Rupees					
16	Arresting leakage of rain water in to wall by applying polymer putty on exterior side of GM chambers including rent of tools required all complete.	1.00	Job		Each	
	(Rupees					
17	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.					
a)	90mm Dia	8.00	mtr		One Metre	
	(Rupees					
						Total:

Signature of the Contractor

Executive Engineer(Civil),
BSNL Civil Division,
Tirupati.